Sl.No.	Items of work	Unit	Quantity	Rate in figures	Rate in words	Amount
				Rs. a. p.	Rs. a. p.	Rs. a. p.
(k)	Forming road with stony gravel with an average lead of half a mile.	C.yds.	25			
(l)	Unforeseen items such as putting up ring bunds and opening out a temporary road, etc.	Lump sum				
	N.B.—Two bridges of 3 vents of 5 feet each are to be constructed.					
II	Constructing a tunnel of 2 vents of 5 feet each.	...	...			
(1)	Earthwork excavation (hard soil)	C.yds.	22			
(2)	Jelly concrete in surki mortar ...	C.ft.	28			
(3)	Burnt stone in surki mortar ...	,,	166			
(4)	Cement pointing ...	Sqr.	1·16			
(5)	Pointing with surki mortar ..	,,	1·28			
(6)	Rough stone work new with jelly	C.yds.	52½			
(7)	Burnt stone slabs roughly dressed at joints and fixed.	S.ft.	150			
(8)	Burnt brick in chunnam ...	C.ft.	65			
(9)	Chunam plastering ...	Sqr.	·73			
(10)	Providing and fixing guard stones top rounded	No.	4			
(11)	Forming road with stony gravel with an average lead of half a mile.	Lump sum				
(12)	For unforeseen expenses such as putting up ring bunds and opening out a temporary road.	,,				
	N.B.—Two tunnels of 2 vents of 5 feet each are to be constructed.					
III	Constructing a tunnel of 1 vent of 4 ft.	..	...			
(1)	Earthwork excavation (hard soil)	C.yds.	9			
(2)	Rough stonework new with jelly.	,,	18			
(3)	Burnt stone slabs roughly dressed at joints and fixed	S.ft.	72			
(4)	Pointing with surki mortar ...	Sqr.	72			
(5)	Providing and fixing guard stones top rounded.	No.	4			
(6)	Forming the road with gravel ...	Lump sum				
(7)	For unforeseen works ..	,,				
	N.B.—Four tunnels of 1 vent of 4 feet each are to be constructed.					
IV	Earthwork for enbankment with lead ½ to ¾ mile for approches, bridges, tunnels, etc.	C.yds.	3,151			
V	Excavating side drains ...	,,	294			
VI	Rooting out grass on road and filling up ruts.	Lump sum				
	Total Rs. ...	..	..			

B. S. PUTTASWAMY,
President,
District Borad.

OFFICE OF THE PRESIDENT, TOWN MUNICIPAL COUNCIL, MANDYA.

Notice dated the 10th November 1935.

Notice is hereby given that sealed tenders will be received at the Office of the President, Town Municipal Council, Mandya, up to 2 P.M. on the 29th November 1935, for constructing a new building for the Municipal Office, at Mandya. An approximate of quantities of the

items of work is given below. These quantities are not guaranteed. The work should be completed by the end of May 1936.

2. The plans and detailed estimate may be seen at the Office of the President, Mandya, between the hours of 11 A.M. to 5 P.M. on all working days.

3. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 600 in cash, as earnest money and be superscribed "Tender for Constructing the Municipal Office Building at Mandya."

5. The final acceptance of any tender will rest with the Municipal Council, Mandya, which does not bind itself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, and begin the work immediately, in default of which, his tender will be considered as cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Municipal President's Office at Mandya. No enquiry regarding the acceptance or rejection of the tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money of rejected tenders will be returned.

9. Rates once tendered, will not be enhanced on any account.

10. Rates for non-tendered, and non-estimated items, shall be as per schedule rates prevailing in the locality, and will be fixed by the President, Municipal Council.

11. Quotations should be given in words as well as in figures and they must be in specific terms for the unit shown against each item of work. Any quotation quoted at so much percentage more or less than the estimated rate will not be accepted.

12. The work should be according to Public Works Departmental specification and standards.

13. Charges on account of scaffolding materials, implements for setting out, barricading supply of water, etc,, that may be found necessary during the execution will not be paid for separately but should be borne by the contractor.

14. Transfer of works to third parties by the selected contractor, or subletting of contracts is prohibited.

15. Monthly progress should not be less than Rs. 1,000 and the work must be completed by the end of May 1936, in default of which the earnest money or a portion thereof will be forfeited at the discretion of the Municipal President and the contract cancelled.

16. In all matters not specifically provided for and in all matters of dispute about rates quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Municipal Council will be final and legally binding.

Abstract of the estimate for Constructing the New Municipal Office Building at Mandya.

No.	Items of work	Quantity	Per	Rate
				Rs. a. p.
1	Earthwork excavation H. G. ...	157	Cyd.	
2	Concrete in lime mortar	1,092	C.ft.	
3	Size stone in mud	2,993	,,	
4	Do mortar	380	,,	
5	Burnt brick in mud	5,418	,,	
6	Steel girders	87½	Cwt.	
7	Burnt stone slabs 9" thick roughly dressed...	51	S.ft.	
8	Jack-arch terrace including centering, etc., complete, etc.	1,479	Sqr.	
9	Teakwood doors with pannel, shutters, hinges, bolts, handle, etc., complete.	180	S.ft.	
10	Teakwood windows with pannel shutters outside, ironbars, hinges, glazed shutters inside etc., complete.	206	,,	

No.	Items of work.	Quantity	Per	Rate
				Rs. a. p.
11	Ventilators with glazed shutters, etc., complete.	96	S.ft.	
12	Plastering with chunam mortar ...	6,213	Sqr.	
13	Whitewashing with two coats ...	6,213	,,	
14	Flooring with 3" concrete, and cement plastering including dividing the area into small squares and painting the whole with red.	1,354	,,	
15	Pointing the basement with cement mortar	338	,,	
16	Burnt stone slabs 6" thick roughly dressed...	439	S.ft.	
17	Pillars including plastering with fine mortar whitewashing, basement, capitals, bond-slabs, etc., complete, with specially prepared bricks in mortar.	5	each *	
17(a)	Do do ...	4	,, †	
18	Parapet including cornice at top and bottom	257	R.ft.	
19	Chacolate painting two coats ...	869	Sqr.	

* 12 x 1½' x 1½ feet.
† 12 x 2¼' x 2¼ feet.

E. V. GANAPATHI IYER,
President.

HASSAN TOWN MUNICIPALITY.

Notice dated 10th November 1935.

1. The public are hereby informed that it is arranged to hold a Cattle Show in the dry lands behind the Musafirkhana and Santhemala at Hassan. The Show will commence on Thursday the 2nd January 1936, and close on the evening of Monday the 6th January 1936.

2. The Cattle Show is intended to give to the raiyats an idea of the several species of cattle breed in and beyond the Hassan District and thus to promote general improvement in the breed of cattle.

3. The several classes of cattle which will be awarded prizes in the Show are given in the appendix.

4. Arrangements will be made to promote competition and to induce cattle owners to exhibit the best cattle available by awarding prizes. Those who desire to have special facilities for sale of cattle are requested to address the President, Hassan Town Municipality, before the opening of the Show.

5. As per Government Proceedings No. L. 2721—Ml. 154-27-5, dated 17th November 1927, a uniform rate of two annas per head of cattle will be levied on all cattle admitted to the Cattle Show enclosure.

6. Fodder will be available for sale near the Show enclosure.

7. Every animal admitted to the Show enclosure should be accompanied by a sufficient number of men to keep it under proper control.

8. Only cattle considered suitable will be allowed to compete in the Cattle Show for prizes and only such cattle as get prizes will be admitted into a special enclosure.

9. No animal which has been awarded one prize will be allowed to compete for any other prize except for a special prize.

10. Working cattle may, at the option of the judges, be subjected to a practical test as to their power of draught, etc.

11. Admission of competing cattle into the Show enclosure will be closed on the evening of the 5th January 1936.

12. All persons who become exhibitors of cattle will be held to have signified their consent and acceptance to the above conditions and to such other conditions which the Committee may hereafter prescribe.

13. For other particulars, enquire in the Town Municipal Office, Hassan